

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 4-35

LOCATION NW NW

SEC. 11 TWP 35S RGE. 32W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. C-1 Lease Light Estate

Operator Jomilson Producers Address R.F.D. #1, Box 142, Liberal, Kansas

Field \_\_\_\_\_ County Seward

Total Depth 6248 Feet.

Plugging Contractor Daco Well Service

Plugging Contractor's License No. 138

Address Borger, Texas

(Describe briefly the manner in which the well was plugged)

Hole full of heavy mud. Set 5247' 5 1/2" casing cemented 150 sacks. Casing was perforated from 5127 to 29 recovered oily salt water, mudded off and set packer plug 5122.

Perforated 5109 to 5112, recovered gas and salt water ran cement retainer and squeezed with 100 sacks cement, cleaned up hole and perforated from 5094 to 5104, recovered just a little gas not commercam. Mudded and plugged back to 5035. Perforated 4995 to 4999 recovered oily salt water mudded and set backer plug 4930 perforated from 4007 to 4009 perforated at 4890 to 4898 recovered oily mud. Acidized with 500 gas acid, recovered salt water, spotted mud on bottom. Shot off 5 1/2" casing, circulated mud and pulled same. Allowed mud to settle spotted 25 sacks of cement at 500 feet in 8-5/8" shot off 8-5/8" at 378 feet. Pulled same

and filled with mud. Welded on steel cap 4' below ground level.

**PLUGGING**  
FILE SEC 11 T 35 R 32W  
BOOK PAGE 4 LINE 35

1-30-54

R. J. Phillippe  
District Conservation Agent

Date December 28, 1953