

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. CSL 7WSE

LOCATION NW SE 1350 from S & 660 from West

SEC. 11 TWP. 35 RGE. 32

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Weiland

Operator Ted R. Lofland Address Liberal, Kansas R F D #2

Field _____ County Seward

Total Depth 7561 Feet.

(Describe briefly the manner in which the well was plugged)

Hole full of mud

- 7561 to 6350' Heavy mud
- 6350 to 6250' Cement (25 sacks)
- 6250 to 6100' Heavy mud
- 6100 to 5900' Cement (25 sacks)
- 5900 to 5600' Heavy mud
- 5600 to 5500' Cement (25 sacks) Set 60 days waiting on contractor.
- 5500 to 2400' Heavy mud
- 2400 to 2310' Cement (25 sacks)
- 2310 to 1095' Heavy mud
- 1095 to 511' Heavy mud, shot off 9 5/8 casing at 490 feet.
- 511 to 475' Cement (30 sacks)
- 475 to 28' Heavy mud
- 28 to 5' Cement, 11 sacks

Cut off pipe and leveled.

All cement was pumped in hole by Halliburton.

R. J. Phillippe
 District Conservation Agent

Date May 10, 1952

RECEIVED

STATE CORPORATION COMMISSION

PLUGGING

FILE SEC 11 T 35 R 32 MAY 10 1952

BOOK PAGE 47 LINE 42 5-17-52

CONSERVATION DIVISION
 Wichita, Kansas