

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Secure Trust

Complete Address: Box 681 Woodward, Okla.

Lease Name Elmer Myers Well No. # 1

Location SE NW Sec. 9 Twp. 35S Rge. 27 (E) (W)

County Meade Total Depth 3150'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Jac-Kaf Inc.

Address: Perrington, Texas (Applied for) License No. \_\_\_\_\_

Operation Completed: Hour 8 PM Day 30 Month 11 Year 65

The Above well was plugged as follows:

10 3/4"-420'-Circulated w/cement. 4 1/2"-3150' Cemented. Top perforations-3000'

Plug bottom w/25 Sax. cement top cement at 2700'. Mud 2700' to 425'.

Spotted 60 Sax. cement 425' to 325'. Mud 325' to 45'

Plug, 25 Sax. cement 45' to 0. Halliburton Cementing Co.

Weld on plate after cutting surface off 3' below ground level.

Pulled 1523' 4 1/2" pipe. Left 810' tubing, 2" and one Baker Model G- In well.

STATE CORPORATION COMMISSION

DEC -2 1965

I hereby certify that the above well was plugged as herein stated.

12.2.65

2321-W

Signed: [Signature]  
Well Plugging Supervisor