

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-15-119-20,476

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Hawkins Oil & Gas Inc.

Complete Address Box 1578, Liberal Kansas 67901

Lease Name This Well No. 1-1

Location C. NE NW Sec. 1 Twp. 35 Rge. 26 (East)(West)

County Meade Total Depth _____

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A ~~_____~~

Other well as hereinafter indicated ~~This well was completed but never produced~~

Plugging Contractor Sargant's Casing Pulling

Address 6205 Lincoln Box 506 Liberal Kansas 67901 License No. _____

Operation Completed: Hour: 11:00 AM Day: 14 Month: May Year: 19 83

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

They set 6324' of 4 1/2" production pipe with cement outside of pipe at 5000'. They plugged back to 6274' Perforated from 5994' to 98'. They plugged bottom with 1 sby of hulls + 20 sby of cement. 2nd plug at 8'25' with 35 sby of cement. Then 3rd plug on solid bridge at 40' to 0' with 10 sby of cement. They pumped the cement through production pipe with hole full of heavy mud. The plugging was accomplished by Sargant's Casing Pullers. (Over)

Amount of Surface Casing: 802' of 8 3/8" Cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1983
5-18-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

5-19-82
T-88-W
129

They recovered 24402' of 4 1/2" production pipe.

Paul A. Lutho