

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20,499-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Hankins Oil & Gas Co.

Complete Address 330 South Boston Tulsa, Oklahoma 74003

Lease Name Heis Well No. 1-8

Location C-W 1/2 of N 1/4 Sec. 8 Twp. 355 Rge. 24 W (East) (West)

County Clark Total Depth 411

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated While drilling the ground sand around here

Plugging Contractor Da Mac Drilling Co. Inc.

Address Box 1164 Sweet Bend Tex. 67530 License No. _____

Operation Completed: Hour: 7:30 PM Day: 24th Month: Sept. Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There is 116' of conductor pipe cement circulated. They had a casing on location & left 12 drill collars 6 1/4" and 2 stands of drill pipe 4 1/2" in hole & a 12 1/4' bit on bottom. We took 1 pipe & washed down to 179' & pumped 325 sks of cement down hole. They put 200 sks of Hestopic & 125 sks of common cement in hole. Then pumped 15 sks down drill pipe & collars. Then put 50 sks down the conductor pipe from top. Mr. Charles Smith was the engineer on the location.

Cementing accomplished by Haliburton Co. of Lehi, Kansas
8116 W

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

Signed: Luther
Conservation Division Agent
CONSERVATION DIVISION
Wichita, Kansas

SEP 28 1981

03010 AM