

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 137-17  
LOCATION 165' FSL 495' FEL  
NW/4  
SEC. 4 TWP. 35S RGE. 23W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1-A Lease G. M. Dunne  
Operator Skelly Oil Company Address Box 1650, Tulsa, Oklahoma  
Field Wildcat County Clark  
Total Depth 6000' Feet.

(Describe briefly the manner in which the well was plugged)

- Plugged back with 50 sacks of cement from 6000' to 5870 feet.
- Plugged back with mud from 5870 feet to 2200 feet.
- Plugged back with 50 sacks of cement from 2200 feet to 2070 feet.
- Plugged back with mud from 2070 feet to 400 feet.
- Plugged back with 30 sacks cement from 400 feet to 360 feet.
- Plugged back with mud from 360 feet to 20 feet.
- Plugged back with 20 sacks of cement from 20 feet to 6 feet.
- Plugged back with surface soil from 6 feet to surface.

**PLUGGING**  
FILE SEC 4 T 35 R 23W  
BOX PAGE 137 LINE 17

JAN 21 1952

*R. J. Phillips*  
District Conservation Agent

Date January 13, 1952