

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Lone Star Exploration, Inc.

Complete Address: 2010 Republic Nat'l Bk. Bldg. Dallas, Texas

Lease Name Noble Cook Well No. 1

Location C NW SW Sec. 9 Twp. 35 Rge. 22 (W)

County Clark Total Depth 5746'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland

Address: Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 5:00PM Day 26 Month 4 Year 1967

The Above well was plugged as follows:

13 3/8" to 425' circulated w/ cement, 8 5/8" to 2480' cemented.

5 1/2" to 5738' cemented No Perf. 8' of open hole.

Plug bottom w/ 25 sacks cement. Top of cement 5638'

Mud 5638' to 475' Spotted 50 Sacks cement 475' to 375'

Mud 375' to 30' Plug, Hulls & 15 sacks cement 30' to 0'

Company Pump. Pulled 1494' of 8 5/8" casing and

3032' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Green  
Well Plugging Supervisor

4/28/67  
5/33-W