

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
(File One Copy)

JUL 22 1985
7-22-85
CONSERVATION DIVISION
Wichita, Kansas

6/86

API NUMBER 15-191-21501-0000 *Old Well (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR BRANDT PRODUCTION COMPANY, INC. OPERATORS LICENSE NO. 5360

ADDRESS 105 S. Broadway, Suite 920, Wichita, KS 67202 PHONE # (316) 267-4335

LEASE (FARM) COTTLE WELL NO. 1-A WELL LOCATION SE SE SW COUNTY SUMNER

SEC. 4 TWP. 35S RGE. 1W (S) or (W) TOTAL DEPTH 4575' PLUG BACK TO 3700' & 4060'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 395' CEMENTED WITH 275 SACKS

CASING SIZE 5-1/2" SET AT 4132' CEMENTED WITH 175 SACKS

PERFORATED AT 3456-60' & 3464-69' in the K.C. & 4008-18' in the Miss.

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE none

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Place 50' of Chat across Kansas City,

Perf. 3456-69' & 5 sx cement on top. Fill with rotary mud to 400'. Fill Surface

casing with 85 sx., 50-50 poz., 6% gel. Cut off Surface Casing at Ground level.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

CLYDE MARTIN PHONE # (316) 321-5670

ADDRESS 1000 S. Atchison, Eldorado, Kansas 67042

PLUGGING CONTRACTOR B & S Well Service LICENSE NO. 6013

ADDRESS P.O. Box 837, Winfield, Kansas PHONE # (316) 221-2030

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Earl O. Brandt
(Operator or Agent)

DATE: July 18, 1985

(2)

THIS WELL WAS PURCHASED BY BRANDT PRODUCTION FROM CITIES SERVICE OIL & GAS

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
EITH R. HENLEY
JUDITH A. McCONNELL
RIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

OCT 22 1985

EXPIRES

July 22, 1985

WELL PLUGGING NOTICE

Cottle #1
SE SE SW
Sec. 4-35S-1W
Sumner County

Brandt Production Co., Inc.
105 S. Broadway, Ste. 920
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to
DIST. #2 202 Century Plaza 111 W. Douglas Wichita, KS 67202 316-262-8330
five days prior to plugging the well (KAR-82-3-113).