

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

15-129-10419-0000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 12-15-54 Spud Date (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 8/94

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Interstate Unit WELL# 67 SEC. 29 T. 34S R. 43 (East/West)

C - SW - SW SPOT LOCATION/0000 COUNTY Morton

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1200' CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4252' CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4188-4126', CIBP @ 4222'

ELEVATION 3513'/3520' T.D. 4252' PSTD 4222' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING TIH w/1-1/4" tbg. Circulate hole w/9 ppg mud. Spot 15 sxs of Class H from 4200-4100'. TOH w/1-1/4" tbg. Pull free point and cut off 5-1/2" csg. Spot 25 sxs cmt @ cut off depth. Spot 60 sxs cmt @ 1300-1100'. Spot 35 sxs cmt @ 650-550'. Spot 15 sxs cmt @ 53-3'. Cut off 8-5/8" csg 3' below ground level and cap. Restore location and contact USFS.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? Filed Drillers Log

If not explain why? APR 28 1994

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: WICHITA, KS

Marvin Johnson PHONE# (316) 697-2188

ADDRESS P. O. Drawer X City/State Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS Rt 1 Box 49BA, Tyrone, OK 73951-9731 PHONE # (405) 854-6575

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4-26-94 AUTHORIZED OPERATOR/AGENT: J. L. Ashton
(signature)

J. L. Ashton, Division Production Manager



Kansas Corporation Commission

Joan Finney, Governor Jim Robinson, Chairman F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 28, 1994

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Interstate Unit #67
API 15-N/A
660 FSL 660 FWL
Sec. 29-34S-43W
Morton County

Dear Marvin Johnson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

William R. Bryson, Director Conservation Division

KCC, Conservation Division, 200 Colorado Derby Bldg., 202 W. 1st St., Wichita, Kansas 67202-1286 (316) 263-3238