

15-129-20565-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-129-20,565-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM) Interstate Unit WELL NO. 95 WELL LOCATION .96' FEL & 1320' COUNTY Morton

SEC. 29 TWP. 34S RGE. 43 ~~NE~~ or (W) TOTAL DEPTH 4281 PLUG BACK TD 4050 w/CIBP

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 1193 CEMENTED WITH 650 SACKS

CASING SIZE 5-1/2 SET AT 4280 CEMENTED WITH 175 SACKS

PERFORATED AT 4105-4120 O.A.

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL CIBP set @ 4050. Dump 20 sxs common cement on top of CIBP. Load hole with lease water. Shoot off casing at freepoint. Spot common cement plugs as follows: 30 sxs at casing cut, 40 sxs from 1250-1100, 35 sxs from 650-480, and 10 sxs from 50-0. Spot 9 ppg mud between each plug located in the surface casing. Cut off casing below ground level and cap well. Restore location.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? sent 2/5/82 IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)

OCT 23 1987
10-23-87 DATE: 10/20/87
M. L. Pease, Division Production Manager
CONSERVATION DIVISION
Wichita, Kansas



Mike Hayden
Keith R. Henley
Rich Kowalewski
MargaLee Wright
Judith A. McConnell

Governor
Chairman
Commissioner
Commissioner
Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

JAN 23 '87

October 23, 1987

EXPIRES

WELL PLUGGING NOTICE

Interstate Unit #95
96' FEL 1320' FNL NE/4
Sec. 29-34S-43W
Morton County

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760