

15-129-10422-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 2/7/55 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) *Interstate Unit WELL NO. 64 WELL LOCATION C NE SE COUNTY Morton

SEC. 29 TWP. 34S RGE. 43 (EX)or(W) TOTAL DEPTH 4278 PLUG BACK TD 4212

Check One:

OIL WELL ☐ GAS WELL ☐ D & A ☐ SWD or INJ WELL ☒ DOCKET NO. 75-605C
C-11,602

SURFACE CASING SIZE 8 5/8 SET AT 1200 CEMENTED WITH 750 SACKS

CASING SIZE 5 1/2 SET AT 4274 CEMENTED WITH 200 SACKS

PERFORATED AT 4196'-4210'

CONDITION OF WELL: GOOD ☐ POOR ☒ CASING LEAK ☐ JUNK IN HOLE ☐

Cmt'd F.G. tbgs.

PROPOSED METHOD OF PLUGGING Pump down cemented fiberglass tbgs w/2 sxs of hulls and 50 sxs

of 65/35 Poz w/8% gel (yld 1.99, wtr 10.9 gal/sx). Down 5 1/2" and 8 5/8" annulus pmp²sxs

of hulls and 120 sxs of 65/35 Poz w/8% gel. Cmt should be to surface on both. Remove csg head

(If additional space is needed use back of form.) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? Log Filed
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P.O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

*Formerly USA "D" No. 4

SIGNED:

J. L. Ashton
(Operator or Agent)

J. L. Ashton - Division Production Mgr.

DATE:

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1991
CONSERVATION DIVISION
Wichita, Kansas



Kansas Corporation Commission

Joan Finney
Governor

Keith R. Henley
Chairman

Rich Kowalewski
Commissioner

Jack Shriver
Commissioner

Judith McConnell
Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

January 24, 1991

Anadarko Petroleum Corp.
P.O. Box 351
Liberal, KS 67905-0351

Interstate Unit #64
C NE SE 29-34-43W
Morton County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801
(316) 225 - 6760

Conservation Division
Shari Feist Albrecht
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238