

15-129-10220-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

15-129-10220-0000 (PLEASE TYPE FORM and File ONE Copy)

API # SPUD 12-29-63 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

5/97

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE SWITZER "A" WELL# 2 SEC. 29 T. 34 S R. 43 (XXXX/West)

170'
- S of - C - NW SPOT LOCATION/QQQQ COUNTY MORTON

1490 FEET (in exact footage) FROM S(N) (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM E(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE SET AT CEMENTED WITH SACKS

PRODUCTION CASING SIZE 7" SET AT 1194' CEMENTED WITH 400 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 1194'-1227' (OH)

ELEVATION 3282 / -- T.D. 1227 PBDT 1227 ANHYDRITE DEPTH --
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS. TH W/ TBG TO PBDT. LOAD HOLE W/ 9 PPG MUD AND EST. CIRC DWN TBG. MIX AND SPOT 2 SXS HULLS AND 32 SX CLASS H CMT FROM 1227'-1127'. TOH WITH TBG TO 610'. SPOT 32 SX CMT FROM 610'-510'. TOH WITH TBG. TO 40'. SPOT 12 SXS CMT 40'-4'. CUT OFF 7" CSG 4' BELOW GL AND CAP. PERMANENTLY INSCRIBE THE DATE OF PLUGGING AND WELL NAME ON TOP OF CAP. RESTORE LOCATION. NOTIFY BLM FOR LOCATION INSPECTION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. TERRY LEWIS PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67950

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6/25/97 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (Signature) DIV. PROD. ENGR.

7-27-97

1/98

ANADARKO PETROLEUM CORPORATION

PHONE 316 - 624 - 6253 • 1701 NORTH KANSAS AVE. • P.O. BOX 351 • LIBERAL, KANSAS 67905 - 0351



June 25, 1997

Kansas Corporation Commission
Conservation Division
Wichita State Office Building
130 South Market, Rm. 2078
Wichita, Kansas 67202-3802

Attn: Priscilla Zadoka

Re: Well Plugging Application (KCC Form CP-1)

Switzer "A" No. 2
Sec. 29-34S-43W
Morton County, Kansas

Dear Ms. Zadoka:

Enclosed in duplicate is a well plugging application (KCC Form CP-1) for the referenced well. Upon approval of this application, please notify this office at the letterhead address so that plugging operations may commence.

If additional information is required, please contact this office at the letterhead address.

Very truly yours,

A handwritten signature in cursive script that reads "John A. Broman".

John A. Broman
Division Production Engineer
JMD/sh

Enclosure

cc: Well File
TRC - HGO
Manager Land Administration - HGO
WI Owners

kccintpa.doc

100-218-001-50
1997 JUN 27 12 12 53



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 27, 1997

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Switzer "A" #2
API 15-N/A
1490 FNL 1320 FWL
Sec. 29-34S-43W
Morton County

Dear Mr. Terry Lewis,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760