

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

15-129-10555-0000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 9-25-55 Drill Date (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P. O. B0x 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Roll WELL# 1-27 SEC. 27 T. 34S R. 43 (East/West)

- - - - - NW SPOT LOCATION/QQQQ COUNTY Morton

1320 FEET (in exact footage) FROM S/(N) (circle one) LINE OF SECTION (NOT Lease Line)

1325 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 587 CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3027 CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2984-89, 2969-74, Plug set at 2959, 2939-44, 2914-44, 2854-58, 2838-42, 2830-34, 2807-11, 2789-2803, 2749-54

ELEVATION 3498 GL T.D. 3027 PSTD 2900 ANHYDRITE DEPTH Not Available
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Mix & pmp 50 sxs cmt plug 2650-2900'. Displace w/65 bbls mud. Pull 5 1/2 csg & shoot off at free point. Pull 5 1/2 csg 50' above cut off. Spot 35 sxs cmt plug at cut off depth (100' plug). Pull 5 1/2 csg to 550' and spot 50 sxs cmt plug 550-650'. TOH w/5 1/2 csg. Spot 10 sxs cmt plug 33-3'. Cut off 8 5/8 csg 3' below ground level and cap well. Restore location.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? - IS ACO-1 FILED? No

If not explain why? Drillers Log Filed

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin Johnson PHONE# (316) 697-2188

ADDRESS Drawer X City/State Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS Rt 1, Box 49BA, Tyrone, Oklahoma 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval RECEIVED NOV 22 1993 INFORMATION COMMISSION 11-22-93

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/9/93 AUTHORIZED OPERATOR/AGENT: David W. Kaplan

David W. Kaplan
Conservation Production Engineer

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

November 22, 1993

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Roll #1-27
API 15-N/A
1320 FNL 1325 FWL
Sec. 27-34S-43W
Morton County

Dear Marvin Johnson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760