

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # SPUD SEPT. 1969 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)  
ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO  
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600  
LEASE KANSAS WELL# 2-23 SEC. 23 T. 34S R. 43W (xxxx/West)  
- NE - SW SPOT LOCATION/QQQQ COUNTY MORTON

1980 FEET (in exact footage) FROM x/§ (circle one) LINE OF SECTION (NOT Lease Line)

3300 FEET (in exact footage) FROM E/x (circle one) LINE OF SECTION (NOT Lease Line)

**Check One:** OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D&A \_\_\_\_\_ SWD/ENHR WELL X DOCKET# D-16491

CONDUCTOR CASING SIZE NONE SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1179 CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE NONE SET AT                      CEMENTED WITH                      SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: CMT PLUG @ 1099-1223 (350 SXS)

ELEVATION 3471 / -- T.D. 4500 PBTD 1099 ANHYDRITE DEPTH             
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL:   GOOD   X   POOR                   CASING LEAK                   JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU. TOY W/ TBG & PKR. LOAD HOLE WITH 9PPG MUD. SPOT  
50 SXS CMT @ 325. SPOT 15 SXS CMT FROM 40 TO SURFACE. CUT OFF 8 5/8 CSG 3' BELOW GL &  
CAP. RDMO AND RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

PHONE# ( )

ADDRESS \_\_\_\_\_ City/State \_\_\_\_\_

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) . . . UPON APPROVAL . . .

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/24/2002 AUTHORIZED OPERATOR/AGENT: Chris K. Walter

DIVISION PRODUCTION ENGINEER



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Anadarko Petroleum Corporation  
17001 Northchase Drive  
Houston, TX 77060

February 25, 2002

Re: STATE OF KANSAS #2-23  
API 15-129-20044-00-01  
NESW 23-34S-43W, 1980 F~~5~~L 3300 FEL  
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely  
A handwritten signature in cursive script, appearing to read "David P. Williams", is written over the word "Sincerely".

David P. Williams  
Production Supervisor