

KANSAS

A
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 1098, Liberal, Kansas

Lease Name Salley "C" Well No. 2

Location NE SW Sec. 16 Twp. 34 Rge. 33 ~~(E)~~ (W)

County Seward Total Depth 6414'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00Pm Day 21 Month 8 Year 1970

The above well was plugged as follows:

8 5/8" to 2794' circulated w/ cement. 5 1/2" to 4175' cemented.

Top perforations 4034' Plug bottom w/ 20 sacks cement.

Top of cement. 3800' Mud 3800' to 900'

Spotted 35 sacks cement 900' to 800'. Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2770' of 5 1/2" casing.

I hereby certify that ^{RECEIVED} the above well was plugged as herein stated.
STATE CORPORATION COMMISSION

AUG 24 1970

CONSERVATION DIVISION
Wichita, Kansas

Signed: *Edgar J. Eden*
Well Plugging Supervisor

INDEXED
8/24/70
INV. NO. 2430-W