

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20598-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Rene Exploration Co.

Complete Address 300 W. Douglas Suite 645 Wichita Kansas 67202

Lease Name Arnold Ranch (East) Well No. 1-32A

Location C-NE/4 Sec. 32 Twp. 34 Rge. 22 (East)(West)

County Clark Total Depth 5740'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor R. & G. Drilling Co.

Address 300 W. Douglas Suite 600 Wichita Kan 67202 License No. _____

Operation Completed: Hour: 1:00 P.M. Day: 25 Month: July Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug 1080' with 40 bbl of cement. 2nd plug at 780' with 35 bbl of cement. 3rd plug at 40' to 50' in solid bridge with 10 bbl of cement. Then they circulated 10 bbl of cement in each the rat hole & mouse hole. The cement was pumped through the drill pipe. The cement used was common with 2% cell & 3% C.C. The plugging was accomplished by Halliburton Co.

Amount of Surface Casing: 738' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

They didn't call back to give me the time they were going to plug.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1982
Conservation Division Agent
SIGNED: Paul A. Luthi

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 7-29-82
AMOUNT 778-w