

*HY*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

Operator's Full Name Shamrock Oil & Gas Corp. DEC 9 1966

Complete Address: Box 631, Amarillo, Texas CONSERVATION DIVISION

Lease Name Lola K. Hilst Well No. 1 Wichita, Kansas

Location 330' FN 330' FE *NE NE NE* Sec. 35 Twp. 33 Rge. 29 ~~(NE)~~ (W)

County Meade Total Depth 5821'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: None

Plugging Contractor: Daco Lease & Well Service

Address: 1700 S. Main St., Borger, Texas License No. 138

Operation Completed: Hour 1:30PM Day 7 Month 12 Year 1966

The Above well was plugged as follows:

9 5/8" to 1547' Circulated w/ cement, 5 1/2" to 5821' cemented.

Top perforations 5692' Plug bottom w/ 20 sacks cement .

Top of cement 5560' Mud 5560' to 1591'

Spotted 40 sacks cement 1591' to 1491' Mud 1491' to 30'

Plug, Halls & 10 sacks cement. 30' to 0'. Co. Pump

Pulled 2650' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward G. Eves  
Well Plugging Supervisor

*12/9/66*  
*4432-W*