

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name Tucker Well No. # 02

Location C SE NE Sec. 19 Twp. 34 Rge. 41 (E) (W)

County Morton Total Depth 5235'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 9 PM Day 11 Month 3 Year 65

The Above well was plugged as follows:

8 5/8"-1527' Circulated w/cement. 5 1/2"-4800' Cemented. Top Perforations-4388'

Plug bottom w/35 Sax. cement top cement 4150'. Mud 4150' to 700'

Spotted 35 Sax. cement 700' to 600' Mud 600' to 45'

Plug, Hulls, 15 Sax. cement 45' to 0 Company Pump. Pulled 2636' 5 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

3/15/65
813-W

Signed: [Signature]
Well Plugging Supervisor