

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name Sleeth Well No. 01

Location C NW SE Sec. 19 Twp. 34 Rge. 42 <sup>41W</sup> (W)

County Morton Total Depth 5203'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 1600P Day 27 Month 5 Year 1968

The Above well was plugged as follows:

8 5/8" to 1516' circulated w/ cement. 5 1/2" to 5135' cemented.

Top perforations 4671' Plug bottom w/ 20 sacks cement

Top of cement 4400' Mud 4400' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3415' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Ford  
Well Plugging Supervisor

INDEXED  
6/4/68  
7855-W