

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Morton
Location: CNE SW Sec. 19 Twp. 34 Rge. 41 (E) (W)
Name of Field: _____ Total Depth: 4750

I have this date completed supervision of plugging of:

Lease Name: O'Dell Well No. 01-19
Operator's Full Name: Gradsko Production Co.
Complete Address: Liberal Kansas
Plugging Contractor: Rueft Quarry Pulley Co.
Address: Grant Bend Road License No. _____
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4 pm Day 3 Month May Year 1961

The above well was plugged as follows:

1408' of 8 5/8" surface casing. Top prof 4686. PBTD 4719'.
Hole was sandbed from 4719' to 4650' and 5 sack
cement dumped for sand. Pulled 477' of 4 1/2" mudbed
pipe to 600'. Set rock bridge from 600' to 590'. Dumped
30 sack cement on bridge. Mudbed pipe to 40'. Set
rock bridge from 40' to 30'. Dumped 10 sack cement
to base of collar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

DATE 6/23/61
FILE NO. 3263-w