

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1963  
8-14-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Panhandle Eastern Pipe Line Company

Complete Address: Box 828 Liberal, Kansas

Lease Name Hill Well No. 1-16

Location C NE Sec. 16 Twp. 34 Rge. 41 (E) (W)

County Morton Total Depth 2320'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sargent Casing Pulling Service Co.

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4 PM Day 10 Month 8 Year 63

The Above well was plugged as follows:

7"-607' Circulated w/cement. 4 1/2"- 2308' Circulated w/cement.

Perforations -2186' to 2196'--2201' to 2206'---2211' to 2219'

Plug bottom w/20 Sax.cement, 1 Sax.hulls, 1 Sax.Jell. 2320' to 2000'

Mud 2000' to 650' 35 Sax.cement spotted at 650' to 500'

Mud 500' to 60' 10' Rock bridge 60' to 50'

15 Sax.cement 50' to surface. Company Pump. Weld cap on surface.

Pulled 790' 4 1/2" Pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: Hugh Scott  
Well Plugging Supervisor

8/14/63  
7578-u