

KANSAS

RECEIVED
STATE CORPORATION COMMISSION
Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

FEB 06 1978

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 129 - 20,350 - 0000 (of this well)

Operator's Full Name Cities Service Company

Complete Address 3545 N.W. 58th St., Oklahoma City, Oklahoma

Lease Name Eagley "A" Well No. 3

Location 1650' FSL & 330' FWL of SW/4 SWNW SW Sec. 11 Twp. 34 Rge. E (W) 41

County Morton Total Depth 5465
3475

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Lohmann-Johnson Drlg.

Address Oklahoma City, Oklahoma License No.

Operation Completed: Hour 12 M Day 2 Month 2 Year 1978

The above well was plugged as follows:

RTD ⁵⁴⁶⁵ 5475' 8 5/8 csg set 1507' cwc Plg. Mat. "Common Cement"

Gunned pits, circulated heavy mud, set 30 sk cmt plug (5370'-5220') thru drill pipe. Heavy mud to 2460' set 75 sk cmt plug (2460'-2250') thru dnill pipe.

Heavy mud to 1557' set 35 sk cmt plug (1557'-1457') thru drill pipe. Heavy mud to 44' set solid bridge & 10 sk cmt plug (44'-4')

I hereby certify that the above well was plugged as herein stated.

Signed: Red Massey
Well Plugging Supervisor

2-8-78
6715-U