

15-129-20129-0000
R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Authority to plug issued
May 4, 1976

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1976
5-13-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Charles B. Wilson, Jr. ^{Hunter}

Complete Address 310 Westhall Bldg, 1616 West Loop South, ⁷⁷⁰²⁹

Lease Name Walsh Well No. 1-29

Location SE, SW. Sec 29 Twp. 33 Rge. (E) (W) ~~X~~

County Morton Total Depth 5560

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Liberal, Kansas License No. 511

Operation Completed: Hour 5:00 PM Day 11 Month May Year 1976

The above well was plugged as follows:

There was 1370' of 8 1/8" surface casing.
The well was plugged back to 3275'
4 1/2" set at 3275'. Perforations were
from 2082-2074. 4 1/2" cemented to 1710'
1st plug at 2100' with 10 sacks cement
& 2 sacks of shells. 2nd plug at 1300'
with 50 sacks cement. 3rd plug at 400'
with 15 sacks cement. There was 1690'

I hereby certify that the above well was plugged as herein stated.

of 4 1/2" salvaged

Signed: Charles Thomas
Well Plugging Supervisor

DATE 5/13/76

INV. NO. 3205-W