

KANSAS

M STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Corp.

Complete Address Box 400, Hugoton, Kansas 67951

Lease Name Burton Well No. 1

Location C SE Sec. 11 Twp. 33 Rge. 40 ~~(E)~~ (W)

County ~~Morton~~ Stevens Total Depth 2620'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor J. D. Well Service

Address Liberal, Kansas License No. 632

Operation Completed: Hour 1:30 PM Day 1 Month 7 Year 1971

The above well was plugged as follows:

12 1/2" to 583' circulated w/ cement. 8 5/8" to 2410' ciru. W/ Cement.

7" Liner 2401' to 2620' Plug bottom w/ 20 sacks cement.

Top of cement. 2330' Mud 2330' to 623'

Spotted 35 sacks cement 623' to 500' Mud 500' to 60'

Plug, Halls & 15 sacks cement 60' to 0' Halliburton Pump Truck

No pipe Pulled

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. [Signature]*
Well Plugging Supervisor

INVOICED

DATE 7/14/71
INV. NO. 3986-41