

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
JUN 26 1969
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Anadarko Production Co.Complete Address: Box 351, Liberal, KansasLease Name A/ Davison "A" Well No. 1Location SW NW Sec. 20 Twp. 33 Rge. 40 (E) (W)County Morton Total Depth 5860'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: NonePlugging Contractor: Lohman-Johnson Drilling Co.Address: 1737 Wichita Plaza, Wichita, Kansas License No. Operation Completed: Hour 8:00PM Day 23 Month 6 Year 1969

The Above well was plugged as follows:

8 5/8" to 1518' circulated w/ cement. Mud 5860' to 5500'Spotted 25 sacks cement 5500' to 5425' Mud 5425' to 900'Spotted 35 sacks cement 900' to 800' Mud 800' to 45'Plug, Halls & 15 sacks cement 45' to 0'.B.J. Cementing Pump Truck, Perryton, Texas

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves

Well Plugging Supervisor

6/26/69
9999-W