

RECEIVED  
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

SEP 7 1982 CONSERVATION DIVISION AGENT REPORT

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15-<sup>1</sup>67 -

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Palaminus Petros

Complete Address Box 18610, Wichita Kansas 67218

Lease Name Carlisle Well No. 2

Location C-SE-SW Sec. 36 Twp. 34 Rge. 36 (East)(West)

County Stevens Total Depth 6610'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Co.

Address Box 699, Hugoton, Kans 67951 License No. \_\_\_\_\_

Operation Completed: Hour: 6:30 PM Day: 1 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

They set 1394' of 8 3/8" plugged back the production pipe that was 4 1/2" set at 6610'. The plug back was at 6578' perforated it from 6522' to 38'. 1st plug pumped to bottom to cover perforations was 1 Sbk hulls + 35 Sbk of cement. 2nd plug was at 1450' with 50 Sbk of cement. 3rd plug was at 45' to 0' with 15 Sbk of cement. Then pumped 75 Sbk of cement down annulus. There wasn't any pipe recovered. Halliburton cementing accomplished the plugging.  
Amount of Surface Casing: 1394' of 8 3/8" cement circulated.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: \_\_\_\_\_  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

9-9-82  
1092-W