

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shell Oil Company
Complete Address 1700 Broadway, Denver, Colorado
Lease Name Matzen Well No. 1-35
Location C SE SE Sec. 35 Twp. 34 Rge. 36 ~~(E)~~ (W)
County Stevens Total Depth 6830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: Swd at a later date.

Plugging Contractor: Lohmann-Johnson

Address: 1737 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 9:00AM Day 18 Month 2 Year 1969

The Above well was plugged as follows:

9 5/8" to 1406' circulated w/ cement. Mud 6830' to 2950'
Spotted 100 sacks cement 2950' to 2665' Mud 2665' to 900'
Spotted 40 sacks cement 900' to 800' Mud 800' to 45'
Plug, Halls & 15 sacks cement 45' to 0'.
Halliburton Pump Truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Enea
Well Plugging Supervisor

2/29/69
9362-u