

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
206 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-129-10395-0000

API NUMBER 5-14-57 Spud Date \_\_\_\_\_

LEASE NAME Interstate Unit

WELL NUMBER 10

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 5/29/57

Plugging Commenced 9/25/94

Plugging Completed 9/27/94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/27/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Drillers Log

Is ACO-1 filed? Filed If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4391

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1200'	4'
				5-1/2"	4390.5'	1260'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Ran 1-1/4" tbg to 4110'. Circ hole w/mud. Spot 10 sxs cmt plg from 4110-4010'. Ld 1-1/4" tbg. Shot csg @ 1260'. came loose. Circ hole w/mud. Spot 50 sxs plg from 1250-1100'. 40 sxs cmt plg from 650-550'. Pull csg to 34'. Rec 33 jts 5-1/2" csg. Spot 10 sxs cmt plg from 34-4'. Cut off 8-5/8" csg & cap 4' below gl. KCC Witness: Glenn Barlow. Restore location & contact USFS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, Oklahoma 73951-9731 Phone: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes

(Address) Leslie I. Barnes, Sr. Tech. Asst. P.O. Box 351, Liberal, KS 67905-0351

RECEIVED


KANSAS CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of October, 19 94

OCT 19 1994

CONSERVATION DIVISION  
WICHITA, KS

My Commission Expires: \_\_\_\_\_



Notary Public