

15-129-10498-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
20 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 2-12-58 Spud Date

LEASE NAME INTERSTATE UNIT

WELL NUMBER 17

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 4-22-58

Plugging Commenced 5-20-94

Plugging Completed 5-26-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, KS 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/20/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filled? Drillers Log filed If not, Is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 7     | 1248   | 3'         |
|           |         |      |    | 4 1/2 | 4319   | 2523'      |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU SARGENTS. TIH W/1 1/2" TBG TO 4130'. CIRCULATE HOLE W/9 PPG MUD. MIX 1 SX HULLS AND 20 SXS CLASS "H" CMT. SPOT CMT FROM 4130-3936'. TOH W/1 1/2" TBG. PULL FREE POINT AND SHOT 4 1/2" CSG @2838' UNABLE TO WORK LOOSE. SHOT AGAIN @ 2523', WORKED 4 1/2" CSG LOOSE. TOH AND LD 2523' OF 4 1/2" CSG. TIH W/1 1/2" TBG TO 2523'. CIRC HOLE W/9 PPG MUD. SPOT 25 SXS CLASS "H" CMT FROM 2523' to 2423'.  
(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731, Phone (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Morton, ss.

Leslie I. Barnes (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes


(Address) Leslie I. Barnes  
P.O. Box 351, Liberal, KS 67905-0351

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 13 1994 SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 94

CONSERVATION DIVISION  
WICHITA, KS

My Commission Expires: \_\_\_\_\_



Notary Public

45 SXS FROM 1348-1148', 25 SXS FROM 650' to 550', PULL 1½" TBG TO 53'. SPOT 10 SXS  
CLASS "H" CMT FROM 53-3'. CUT 7" CSG 3' BELOW GROUND LEVEL AND CAP. RDMO SARGENTS.  
STATE WITNESS: GLENN BARLOW. RESTORE LOCATION AND CONTACT USFS.

[Faint, illegible text or stamp]