

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20557-0000

LEASE NAME Interstate Unit

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 87

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 43 ~~XXX~~or(W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 3-25-83

Character of Well Oil

Plugging Commenced 4-4-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-8-93

The plugging proposal was approved on 4-3-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation Interstate Purdy Depth to Top 4171 Bottom 4178 T. 4280

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled
				8 5/8	1205	0
				4 1/2	4280	2535

RECEIVED
KANSAS CORPORATION COMMISSION
APR 28 1983
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH w/1 1/4 workstring to 4100'. Circ hole w/mud. Pmp 1 sk hulls & 20 sxs cmt from 4100-3900'. TOH w/1 1/4 workstring. Pull free point and cut off 4 1/2 csg @ 2535'. Pmp 30 sxs from 2500-2400'. Pmp 40 sxs from 1240-1140'. Pmp 30 sxs from 650-550', pull 39 jts of 4 1/2 csg. Pmp 10 sxs from 40-0'. Cut off & cap 8 5/8 csg 3' below ground level. KCC witnessed. Restore (if additional description is necessary, use BACK of this form.) location.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Tech. Asst. P.O. Box 351, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 93

Cheryl Steers
Notary Public

My Commission Expires:

