

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10194-2000

API NUMBER 15-129-10,194

LEASE NAME Humble "A"

WELL NUMBER 5

2130 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 43 ~~EXOR~~(W)

COUNTY Morton

Date Well Completed 12-31-63

Plugging Commenced 2-25-93

Plugging Completed 2-26-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-24-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Red Cave Depth to Top 1264 Bottom 1297

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
				7"	1264	0
				5 1/2"	1297	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set MIRU. Mixed 20 bbl mud, pmp 2 sxs hulls & 20 sxs Common cmt, plug from 1264-1164. Fill hole w/mud to 700'. Pmpd 30 sxs cmt plug from 700-600'. Fill hole w/mud to 50'. Pmp 10 sxs cmt plug from 50' to GL. Cut off & cap 4' below ground level. Restore location. KCC witness - Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kanas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams, Technical Asst.
(Address) P.O. Box 351, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 93

Cheryl Steers
Notary Public

My Commission Expires: _____



13-129-10194-0000

DRILLER'S LOG

WELL NAME Humble #3 COMPANY OPERATING Anadarko Production Company
 ADDRESS of COMPANY Box 351, Liberal, Kansas
 WELL LOCATION 1/4 1/4 1/4,
1130 ft. North of South line,
660 ft. East of West line; Sec. 17 Twp. 34 Rge. 43, Horton County, Kansas
 DRILLING STARTED 12-19, 19 63 DRILLING COMPLETED 12-31, 19 63
 WELL COMPLETED 12-31, 19 63 WELL CONNECTED _____, 19 _____
 ELEVATION 3573.04 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Red Cave			Open Hole	Natural	

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
7"	1-6"	400	2700

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Barren Sand & Clay	0	168			
Red Bed & Gypsum	168	715			
Red Bed	715	875			
Anhydrite	875	1000			
Anhydrite & Sand	1000	1261			
Anhydrite	1261	1297			
Total Depth	1297				

RESULTS of INITIAL PRODUCTION TEST: 1526 MCF/D SIP 3100 psig

STATE RECEIVED
 DIVISION
 JAN 11 1964
 LIBERAL, KANSAS