

15-129-10487-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT\*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 13

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE# ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 5/22/57

Character of Well Input

Plugging Commenced 9/9/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/17/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Drillers Log if not, is well log attached? NA

Producing Formation Purdy Morrow Depth to Top 4246 Bottom 4276 T.D. 4366

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	4246	4276	7	1200	0
Converted to Injection July 1981				4.5	4366	2503

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP at 4200'. Spot 20 sxs cement from 4200-3800'. Shot off casing at 2503'. Spot 30 sxs cement from 2503-2332', 35 sxs cement from 1300-1100', 25 sxs cement from 650-470', and 10 sxs cement from 70-3'. Cap well. All cement plugs are 60/40 Poz with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Engineer (Employee of Operator) or ~~Company~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

\*Formerly Panhandle Eastern Pipe Line Company - HUMBLE No. 3.

(Address) Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 86

BEVERLY J. WILLIAMS  
Seward County, Kansas  
My Appt. Exp. \_\_\_\_\_  
My Commission Expires \_\_\_\_\_

Beverly J. Williams  
Notary Public

November 21, 1986

OCT 8 1986