

15-129-10485-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT *

WELL NUMBER 16

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 43 (K) or (W)

COUNTY Morton

Date Well Completed 3/25/58

Plugging Commenced 9/10/86

Plugging Completed 9/19/86

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Drillers Log If not, is well log attached? NA

Producing Formation Purdy Morrow Depth to Top 4236 Bottom 4266 T.D. 4341

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	4236	4266	7	1264	0
				4.5	4340	1530
Converted to Injection	12/21/79					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP at 4190'. Spot 20 sxs cement from 4190-3790'. Shot off casing at 2003'-no recovery. Shot off casing at 1530'. Spot 35 sxs cement from 1300-1100'. Spot 25 sxs cement from 650-470'. Spot 10 sxs cement from 70-3'. Cut off casing. Weld on cap. All cement plugs are 60/40 Poz with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.


M. L. Pease, Division Production Engineer (Employee of Operator) or ~~COMMISSIONER~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, Kansas 67901

*Formerly Panhandle Eastern Pipe Line Company - HUMBLE 02.

SUBSCRIBED AND SWORN TO before me this 17th day of NOVEMBER, 1986



Beverly J. Williams
Notary Public

November 21, 1986

OCT 8 1986