

15-129-10396-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Interstate Unit*

WELL NUMBER 9

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 17 TWP. 34 SRGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 9/23/57

Plugging Commenced 12/28/87

Plugging Completed 1/4/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/23/87 (date)

by Paul Luthie (KCC District Agent's Name).

Is ACO-1 filed? NA If not, Is well log attached? Drillers Log Attached

Producing Formation Morrow Depth to Top 4298 Bottom 4332 T.D. 4385

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>0</u>	<u>1243</u>	<u>8-5/8</u>	<u>1243</u>	<u>0</u>
		<u>0</u>	<u>4385</u>	<u>5-1/2</u>	<u>4385</u>	<u>2416</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP set @ 4200. Spotted 20 sxs common cmt 4200-4050, on top of CIBP. Load hole with lease water. Shot off csq @ 2416. Spotted 30 sxs cmt 2400-2300. Spotted 60 sxs cmt 1325-1175. Spotted 70 sxs 650-480. Pushed wooden wiper plug to 80. Pmpd 20 sxs cmt from 80-0. Cut off csq 3' below surface and capped well. 9 ppq mud spotted between each plug.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547


Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) P. O. Box 351, Liberal, KS 67905



Subscribed and sworn to before me this 20th day of January, 1988
Beverly J. Williams
Notary Public
State of Kansas

*Formerly J. M. Huber Corp.
GOVERNMENT "A" No. 3

JAN 29 1988
1-29-88
CONSERVATION DIVISION
Wichita, Kansas

WELL RECORD--(Continued,

(5) TORPEDO RECORD

DATE	QUARTS	LIQUID OR GELATINE	FROM	TO	SHELLS			ANCHOR	BOMB	OIL		WATER	
					NO.	SIZE	LENGTH			BEFORE	AFTER	BEFORE	AFTER
	Perforated		4332-30'	w/8			shots per ft.						
			4318-20'	w/4			shots per ft.						
			4306-18'	w/4			shots per ft.						

(6) SWABBING RECORD (7) PLUG BACK RECORD

FROM	TO	DATE	MATERIAL USED	FROM	TO	REMARKS

(8) PACKERS

DATE	DEPTH	PACKER	REMARKS

(9) CLEAN-OUT RECORD

DATES	DEPTH	BAILER OR TOOLS	RESULTS

(10) DEFLECTION

DEPTH	ANGLE	V. CORR.
176'	1/2	
532'	1/2	
812'	1	
1170'	0	
1945'	1/2	
2440'	1/2	
3055'	1/2	
4087'	1/2	

(11) PLUGGING RECORD

START _____ 19 _____ FINISH _____ 19 _____

GIVE RECORD OF PLUGS DRIVEN, CEMENT, ROCK, ETC., MUD AND HOW PLACED, AND ALL PIPE LEFT IN HOLE. (USE NEXT PAGE IF NECESSARY.)

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1988

CONSERVATION DIVISION
Wichita, Kansas

WELL RECORD—(Continued)

WELL NO. #3

LEASE Government "A"

(12) ADDITIONAL INFORMATION

No D.S.T.

(13) MATERIAL LOST IN HOLE

None

(14) WELL LOG

FORMATION	FROM	TO	NO. OF FEET	DRILL. TIME	FORMATION	FROM	TO	NO. OF FEET	DRILL. TIME
Sand, gravel	0	195							
Red bed	195	300							
Red bed, shells	300	752							
Red bed, lime	752	858							
Red bed, sand	858	1095							
Red bed, shells, lime str.	1095	1118							
Anhydrite	1118	1240							
Lime	1240	1255							
Lime, shale	1255	3532							
Lime	3532	3600							
Lime, shale	3600	4019							
Lime	4019	4182							
Lime, shale	4182	4247							
Shale	4247	4285							
Sand, shale	4285	4381							
Shale	4381	4385							
Total Depth	4385								

RECEIVED STATE CORPORATION COMMISSION

JAN 29 1988

CONSERVATION DIVISION
Wichita, Kansas

