

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 3/20/57

LEASE NAME Interstate Unit

WELL NUMBER 14

3300' Ft. from S Section Line

660' Ft. from E Section Line

SEC. 17 TWP. 34 SRGE. 43 (S) or (W)

COUNTY Morton

Date Well Completed 3/20/57

Plugging Commenced 10/27/89

Plugging Completed 11/1/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/27/89 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? NA If not, Is well log attached? Physical Productivity Report filed.

Producing Formation Purdy Morrow Depth to Top 4272 Bottom 4314 T.D. 4360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	4272	4314	8 5/8"	1275	0
				4 1/2"	4356	2626

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 2 sxs hulls and 30 sxs cmt @ 4314-4072, shot off 5 1/2" csg at 2626. Spot 25 sxs cmt at 2600-2500, spot 50 sxs cmt at 1200-1050, spot 35 sxs cmt at 650-480, spot 10 sxs cmt 33-3. Cut off and cap 3' below ground level. Weld on steel plate. Type of cmt used common.
Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation JAN 9 1990

STATE OF Kansas COUNTY OF Morton, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) M. L. Pease
Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 5th day of January, 1990

My Commission Expires:



Notary Public