

15-129-10493-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT\*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 20

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 17 TWP. 34 RGE. 43 (X) or (W)

COUNTY Morton

Date Well Completed 11/9/56

Plugging Commenced 9/25/87

Plugging Completed 9/29/87

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? Driller's Log Attached

Producing Formation Morrow Depth to Top 4225 Bottom 4238 T.D. 4310

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To   | Size   | Put In | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| Morrow    | Oil     | 0    | 1138 | 7"     | 1138   | -0-        |
|           |         | 0    | 4304 | 4-1/2" | 4304   | 2030       |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP set @ 4100. Spotted 25 sxs common cmt 4100-3800 on top of CIBP. Loaded hole w/lease water. Shot off csq @ 2030, spotted 30 sxs cmt from 2000-1900, spotted 40 sxs cmt 1200-1100, spotted 35 sxs cmt 650-500, push wooden wiper plug to 50, pmp 10 sxs cmt from 50-3. Cut off csq and capped well. 9 ppg mud spotted between each plug.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547


Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

\*Formerly Panhandle Eastern Pipe Line Co. (Signature) M. L. Pease

Interstate "B" No. 02 (Address) P. O. Box 351, Liberal, Kansas 67901



SUBSCRIBED AND SWORN TO before me this 9<sup>th</sup> day of November, 19 87  
Beverly J. Williams  
Notary Public, Registered  
STATE CORPORATION COMMISSION

11-12-87 NOV 12 1987 Form CP-4 Revised 07-86

CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOGWell Name Interstate B-C2

Page 2 (Con't)

Well Location Section 17-3/8-43WROTARY LOG

|                |      |      |
|----------------|------|------|
| Shale          | 4245 | 4266 |
| Shale and sand | 4266 | 4310 |

FORMATION TOPSPERFORATIONS

|              |      |
|--------------|------|
| Wabaunsee    | 2518 |
| Topeka       | 2718 |
| CSO Lansing  | 2958 |
| Lansing      | 3146 |
| Marmaton     | 3726 |
| Cherokee     | 3634 |
| Morrow Shale | 4148 |
| Purdy Sand   | 4226 |

4225 - 4230

WELL TREATMENT RECORD

Well not treated.

CASING RECORD

Set 140' 10-3/4" conductor pipe w/250 sx cmt.

Set 1137' of 7" surface casing w/450 sx. cmt.

Set 4304' of 4 1/2" production casing w/400 sx Pozmix cmt.

Ran 4247' of 2-3/8" tubing.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 24 1987