

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10484-0000

API NUMBER 6-9-56

LEASE NAME Interstate Unit *

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 22

660 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 17 TWP. 34S RGE. 43 ~~W~~or(W)

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 6-25-56

Character of Well Input

Plugging Commenced 4-27-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-29-92

The plugging proposal was approved on 4-26-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4242 Bottom 4258 T.D. 4360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put in	Pulled out
				7"	1198	0
				4 1/2"	4310	2210

KANSAS CORPORATION COMMISSION
MAY 19 1992
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH W/1-1/4" tbg to 4200', circ hole w/mud. Mix 15 sxs cmt & spot plug @ 4200-4100', TOH w/1-1/4" tbg. Shot 4-1/2" csg @ 2210', free @ 2210'. Pmp 25 sxs cmt @ 2200-2100', 30 sxs cmt @ 1230-1130', 30 sxs cmt @ 650-550', 10 sxs cmt @ 40-3'. Cut off 7" csg below ground level & cap. Rec 70 jts 4-1/2" csg. KCC Witness - Glenn Barlow. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Eng. Tech. P.O. Box 351, Liberal, KS 67905-0351

*Formerly Panhandle Eastern Pipe Line Company
Humble No. 01

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 92

Cheryl Steers

My Commission Expires: _____

CHERYL STEERS
Notary Public
My Appt. Expires 6-1-93