

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 10-5-57

LEASE NAME Interstate Unit

WELL NUMBER 7\*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4620 Ft. from S Section Line

4420 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 17 TWP. 34S RGE. 43 (E or W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 10-12-57

Character of Well Input

Plugging Commenced 4-17-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-21-92

The plugging proposal was approved on 4-16-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 4284 Bottom 4315 T.O. 4350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size  | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 1229   | 0          |
|           |         |      |    | 5 1/2 | 4350   | 2405       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU PU. Rel Pkr. Pmp 1 sk hulls & 15 sxs cmt to perms @ 4284-4084, pull 10 jts, circ mud. Load 136 jts 2-3/8 tbg (4215). Shot csg @ 2630 would not come loose. Shot @ 2405, free @ 2405. Pmp 25 sxs cmt @ 2400-2300, 30 sxs cmt @ 1250-1150, 30 sxs @ 650-550, 10 sxs @ 40-3'. Cut off 8-5/8 csg 3' below ground level. Rec 71 jts(2405') 5-1/2 csg. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereon set forth, and the log of the above-described well as filed that the same are true and correct, so help me God.

MAY 4 1992

(Signature) Beverly J. Williams  
(Address) Beverly J. Williams, Eng. Tech.  
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 92  
WICHITA, KS

Cheryl Steers  
Notary Public

My Commission Expires:

