

15-129-10496-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 3-30-57

LEASE NAME Interstate Unit

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 21

660
1320 Ft. from S Section Line

3300
660 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 17 TWP. 34S RGE. 43 ~~XXX~~(W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 4-6-57

Character of Well Oil

Plugging Commenced 4-9-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-9-92

The plugging proposal was approved on 4-8-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4203 Bottom 4213 T.D. 4260
4290

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1138	0
				4 1/2	4260	2216'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Pmp 1 sx hulls & 20 sxs cmt to perfs 4203-4003', circ hole 2/mud. TOH w/2-7/8" tbg. Shot 4-1/2" csg @ 2426 & 2216, free @ 2216'. Spot 25 sxs cmt 2200-2100'. Pull 4-1/2" csg to 1170'. Spot 30 sxs cmt @ 1170-1070. Spot 30 sxs cmt @ 650-550'. Spot 10 sxs cmt @ 40-3'. Cut off & cap 8-5/8" csg 3' below ground level. Kcc witness - Glenn Barlow. Restore location.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

KANSAS CORPORATION COMMISSION

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Eng. Tech.
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 21 day of April, 19 92

4-23-92

CONSERVATION DIVISION

My Commission Expires: _____

CHERYL STEERS
Notary Public
My Appt. Expires 6-1-93