

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT*

WELL NUMBER 18

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 16 TWP. 34 SRGE. 43 (E or W)

COUNTY Morton

Date Well Completed 12/22/56

Plugging Commenced 5/29/87

Plugging Completed 6/1/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Drillers Log

Is ACO-1 filed? Filed If not, Is well log attached? yes

Producing Formation Purdy Morrow Depth to Top 4184' Bottom 4227' T.D. 4300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	4184'	4227'	7"	1179'	-0-
				4.5"	4300'	1396'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
CIBP @ 4110'. Spotted 20 sxs cement through tubing from 4110' to 3960'. Cut off 4.5" casing at 1396'. Spotted 50 sxs cement from 1280' to 1080', 25 sxs cement from 650' to 470' and 10 sxs cement from 70' to 3'. Cut off and capped 7" casing 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

David W. Kapple, Division Production Engineer (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David Kapple

(Address) P. O. Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 21st day of July, 19 87

Beverly J. Williams
Notary Public, V.L.D.
STATE CORPORATION COMMISSION

My Commission Expires: November 24, 1990

*Formerly Panhandle Eastern Pipe Line Interstate "C" No. 05