

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20558-00-00

LEASE NAME INTERSTATE UNIT

WELL NUMBER 88

10 Ft. from S Section Line

1300 Ft. from E Section Line

SEC. 16 TWP. 34 RGE 43 (E) or (W)

COUNTY MORTON

Date Well Completed 12-8-81

Plugging Commenced 10-17-01

Plugging Completed 10-19-01

RECEIVED
NOV 16 2001
KCC WICHITA

NOTICE: TYPE OR PRINT
Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well INJECTION

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-10-01 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation PURDY MORROW Depth to Top 4133 Bottom 4150 T.D. 4250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
PURDY MORROW	OIL	4133	4150	8 5/8	1192	0
				5 1/2	4248	1228

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. CIRC WITH 9PPG MUD. PUMP 10 SXS CMT FROM 4100-4000. SHOOT OFF 5 1/2 CSG @ 1228. PUMP 50 SXS CMT FROM 1220-1070. PUMP 40 SXS CMT FROM 600-480. PUMP 10 SXS CMT FROM 40 TO SURFACE. CUT OFF AND CAP 8 5/8 CSG 3' BELOW GL.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



Craig R. Walters (Signature)
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 12 day of October, 2001

Lori Pearson (Signature)
Notary Public

My Commission Expires: 2/26/05

OR