

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10499-001

API NUMBER 11-15-56 Spud Date

LEASE NAME INTERSTATE UNIT

WELL NUMBER 25

660 Ft. from S Section Line

1980 Ft. from ^(W)X Section Line

SEC. 16 TWP. 34SRGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 12-4-56

Plugging Commenced 5-13-94

Plugging Completed 5-19-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, KS 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/13/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? ^{Drillers Log} filed If not, is well log attached?

Producing Formation None Depth to Top Bottom T.D. 4290'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7		3'
				4 1/2		2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
MIRU PU. REL PKR. TOH W/132 JTS 2 3/8" TBG & PKR. REMOVE PKR & TIH W/2 3/8" TBG W/SN OPEN-ENDED.
RDMO PU. MIRU SARGENTS. CIRC HOLE W/9 PPG MUD. SPOT 2 SXS HULLS & 20 SXS CLASS "H" CMT FROM 4176-3976'. TOH & LD 2200' of 2 3/8" TBG. TOH W/2 3/8" TBG & LD. PULL FREE POINT & SHOT 4 1/2" CSG & 2700'. WORKED LOOSE AND TOH & LD 1600' OF 4 1/2" CSG. TOH & LD 4 1/2" CSG, 92 JTS IN ALL.

(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731, Phone (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Morton, ss.

Leslie I. Barnes (Employee of Operator) or ~~KXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

KANSAS CORPORATION COMMISSION

(Signature) Leslie I. Barnes

Leslie I. Barnes, Sr. Tech. Asst.
(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1994

1-13-94
CONSERVATION DIVISION

WICHITA, KS Commission Expires:



Notary Public

TIH W/2 3/8" TBG TO 2330', CIRC HOLE W/9 PPG MUD. SPOT 25 SXS CLASS "H" FROM 2330'-
2230', 45 SXS CMT FROM 1260-1060', 25 SXS CMT FROM 660-550', 10 SXS CMT FROM 53-3'.
CUT 7" CSG 3' BELOW GROUND LEVEL AND CAP. RDMO SARGENTS. STATE WITNESS: GLENN BARLOW.
RESTORE LOCATION AND CONTACT USFS.