

15-129-10506-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 3-10-57

LEASE NAME Interstate Unit *

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 15

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 16 TWP. 34S RGE. 43 ~~XXX~~or(W)

COUNTY Morton

Date Well Completed 4-23-57

Plugging Commenced 8-22-91

Plugging Completed 8-23-91

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-21-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Morrow Depth to Top 4256 Bottom 4286 T.D. 4385

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	1230	0
				4 1/2"	4330	1242'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set MIRUCP. TIH w/1-1/4 WS. Circ hole w/9.0 ppg mud. Spot 1 sx hulls & 20 sxs cmt from 4250-4050. Shot 4 1/2" @ 1242. Spot 50 sxs cmt from 1242-1142, spot 30 sxs from 650-550. Ld 41 1/2 jts of 4 1/2 csg. Pmp 10 sxs cmt from 33-3'. Cut off & cap csg. Witnessed by State Rep - Glenn Barlow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams - Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams
(Address) Beverly J. Williams - Eng. Tech. P.O. Box 351, Liberal, KS 67905-0351

*Formerly APC Interstate "C" No. 08

STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 91

Cheryl Steers
Notary Public

SEP 18 1991

My Commission Expires: _____
Wichita Kansas

