

API NUMBER 15-129-21640-0000
 LEASE NAME USA INTERSTATE "A"
 WELL NUMBER 1

RECEIVED
 SEP 04 2001

NOTICE: TYPE OR PRINT
 Fill out completely
 and return to Cons. Div.
 office within 30 days

1880 Ft. from S Section Line
860 Ft. from E Section Line
 SEC. 16 TWP. 34S RGE 43 (E) or (W)
 COUNTY MORTON
 Date Well Completed 6-21-2001
 Plugging Commenced 6-21-2001
 Plugging Completed 6-22-2001

LEASE OPERATOR KCC WICHITA ANADARKO PETROLEUM CORPORATION
 ADDRESS 701 S. TAYLOR, SUITE 400, AMARILLO, TEXAS 79101
 PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-21-2001 (date)
 by MR. SCOTT ALBERT (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 4525

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1308'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. TIH W/4 1/2" DP TO 2300' & SPOT 100 SKS 60/40 POZMIX, 6%GF @ 2300', TOH TO 1408' & SPOT 75 SKS, TOH TO 600' & SET 40 SKS, TOH TO 40' & SET 10 SKS FROM 40' TO 0'. SET 10 SKS IN MH & 15 SKS IN RH. CUT OFF 8-5/8" CSG 3' BELOW GL AND CAP, PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DOWELL-SCHLUMBERGER License No. 116095

Address 204 S. MISSOURI, ULYSSES, KANSAS 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, ENGINEERING TECHNICIAN III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) L. Marc Harvey

(Address) L. MARC HARVEY, ENGINEERING TECHNICIAN III
 701 S. TAYLOR, SUITE 400, AMARILLO, TX, 79101

SUBSCRIBED AND SWORN TO before me this 29 day of August, 2001

Lori Pearson
 Notary Public

My Commission Expires: 2/26/05

OR