

Your Copy

LEASE NAME Red Cave

TYPE OR PRINT

WELL NUMBER 3

NOTICE: Fill out completely
and return to Cons. Div. ELH-TULSA D.O.
office within 30 days.

1250 Ft. from N Section Line

FEB 11 11:25 AM '93 from E Section Line

LEASE OPERATOR Edgar White

SEC. 18 TWP. 34 RGE. 43W (E) or (W)

ADDRESS 701 Vilymaca Street Elkhart, Kansas 67950

COUNTY Morton

PHONE (316) 697-2163 OPERATORS LICENSE NO. 5156

Date Well Completed _____

Character of Well _____

Plugging Commenced 1-7-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-7-93

The plugging proposal was approved on 1-7-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 1279

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	410	0
				5 1/2	1256	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pump 25 sks. of cement & 2 sks. of hulls from 1279' to 1100'

Pump 35 sks. of cement & 2 sks. of gel from 450 to 300'

Mix 1 sk. of gel & 10 sks. of cement from 60 to 0'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Edgar White

FEB 24 1993

STATE OF Kansas COUNTY OF Morton, ss. EDGAR W. WHITE CONSERVATION DIVISION
Wichita, Kansas

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed in the office of the State Corporation Commission and the same are true and correct, so help me God.

(Signature) Edgar White

(Address) 701 VILYMACA P O DRAWER "0" ELKHART KS 67950

15th JANUARY 1993

KARENE KNEPP
Notary Public - State of Kansas
My Appt. Expires 8-4-96

AND SWORN TO before me this _____ day of _____, 19 _____

AUGUST 4, 1996

Glenn E. Knepp
Notary Public

My Commission Expires: _____

15-129-20403-0000

KANSAS


WELL COMPLETION REPORT AND DRILLER'S LOG

S. 18 T. 34 R. 43 ^W

Loc. A C SE

County Morton

640 Acres
N



Elev.: Gr. 3536

DF _____ KB _____

API No. 15 — 129 — 20,403
County Number

Operator

Edgar W. White

Address

701 Vilymaca Street Elkhart, Ks. 67950

Well No.

#3

Lease Name

Red Cave Interstate

Footage Location

1250 feet from (N) ~~line~~ line 1250 feet from (E) ~~line~~ line

Principal Contractor

Gabbert Jones Inc.

Geologist

Spud Date

9-29-79

Date Completed

7-30-80

Total Depth

1279

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

None

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4'	8 5/8'	20	1256'	Halliburton	325	Class H 3% CC
Long String	7 7/8"	5.5"	14.5	1256'	Halliburton	250 75	Howcolite Class H

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			open hole		1256-1279'

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Drilled open hole with cable tool from bottom of casing to 1279'. Foam frac w/20,000 gal 80 quality foam w/ 3% gelled acid and 200 sks 10-20 sand	1256' to 1279'

RECEIVED
STATE CORPORATION COMMISSION

Kansas Corporation Commission

INITIAL PRODUCTION

K S No. 68740

NOV 9 1992

Date of first production

not on line

Producing method (flowing, pumping, gas lift, etc.)

flowing with pumping unit

RATE OF PRODUCTION PER 24 HOURS

Oil

Gas

Water

Gas-oil ratio

bbls.

12

MCF

50

bbls.

Disposition of gas (vented, used on lease or sold)

gas not sold

Producing interval(s)

1256'-1279'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Edgar W. White

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Gas

Well No.

3

Lease Name

Interstate Red Cave #3

S 18 T 34 R 43 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

See copy of Drillers Log attached log

No electric/was run since well was open Hole completed

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Owner

Title

7-30-80

Date

REPUBLIC

15-129-20403-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Interstate Red Cave #3
75' Eof SE/4 Sec 18-348-43W
Morton County Kansas

Commenced: 9-29-79

Completed: 10-1-79

OPERATOR: Edgar W. White

Depth		Formation	Remarks
From	To		
0	414	Sand	Ran 10 jts of 20# 8 5/8" csg set @ 410' Cemented w/ 325 sks Class H - 3% CC PD @ 12:45 a.m. 9-30-79 Ran 35 jts of 14# 5 1/2" csg set @ 1256' Cemented w/ 250 sks Howcolite 75 sks Class H PD @ 8:00 p.m. 10-1-79
414	728	Sand-Redbed	
728	1167	Sand	
1167	1257	Sand-Shale	
	1257 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me before me this 10th day of October, 1979.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1979



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Interstate Red Cave #3
 75' Eof SE/4 Sec 18-34S-43W
 Morton County Kansas

Commenced: 9-29-79

Completed: 10-1-79

OPERATOR: Edgar W. White

Depth		Formation	Remarks
From	To		
0	414	Sand	Ran 10 jts of 20# 8 5/8" csg
414	728	Sand-Redbed	set @ 410' Cemented w/
728	1167	Sand	325 sks Class H - 3% CC
1167	1257	Sand-Shale	PD @ 12:45 a.m. 9-30-79
	1257 - TD		Ran 35 jts of 14# 5 1/2" csg
			set @ 1256' Cemented w/
			250 sks Howcolite 75 sks
			Class H
			PD @ 8:00 p.m. 10-1-79

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me before me this 10th day of October, 1979.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

