

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

6-4

API NUMBER 15- 025-20,166-0000
C NE NW, SEC. 13, T 35 S, R 21
4620 feet from S section line
3300 feet from E section line

L

TECHNICIAN'S PLUGGING REPORT

Operator License # 30417
Operator: AEXCO Petroleum, Inc.
Name & Address: 1015 Waterwood Parkway, Ste. G
Edmond, OK. 73034

Lease Name Tuttle Well # 11-116
County Clark 195.00
Well Total Depth 6000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 714

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1:30 p.m. Day: 4 Month: 6 Year: 19 97

Plugging proposal received from Kirby Lillard

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5729' w/200 sx cement, Perfs at 5577-82, 5592-94', Anhydrite Base 2350'

1st plug pump 20 sx cement and 1 sx hulls on bottom,

2nd plug at 970' with 25 sx cement, 3rd plug at 730' with 50 sx cement,

4th plug at 300' with 20 sx cement,

5th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1997

CONSERVATION DIVISION
Wichita, Kansas
Scott Alber (TECHNICIAN)

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 4 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement with 2 sx hulls through tubing over

perfs, pulled all casing out of hole and ran tubing to 970', circulated with mud,

2nd plug pumped 20 sx cement at 970',

3rd plug pulled to 730' and pumped 50 sx cement,

4th plug pulled to 300' and pumped 20 sx cement,

5th plug pulled out of hole and filled with 10 sx cement.

Remarks: Used common cement by Sargents. Recovered 4440' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed _____ (TECHNICIAN)

48323
6-4