

NOV 24 1992

15-129-10194-0000

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE COPY) CONSERVATION DIVISION  
WICHITA, KS

API # 15-129-10194 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549 8-93  
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Humble "A" WELL# 5 SEC. 17 T. 34S R. 43 (East/West)

150'-N of G-NW - SE SPOT LOCATION/QQQQ COUNTY Morton

2130 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 7" SET AT 1264 CEMENTED WITH 450 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 1297 CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 1264-1297'

ELEVATION 3573.04 T.D. 1297 PBDT 1297 ANHYDRITE DEPTH 1297  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Ld hole w/9 ppg mud and establish injection dwn 5 1/2" csg.

Spot 2 sxs hulls and 20 sxs cmt @ 1297-1214. Spot 10 sxs cmt @ 40-3'. Cut 7" csg off 3'

below ground level and cap csg. Restore location.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? - IS ACO-1 FILED? Filed Drillers Log

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin Johnson PHONE# (316) 697-2188

ADDRESS Drawer X City/State Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent's Casing Pulling Service KCC LICENSE # 6547 6-93  
(company name) (contractor's)

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11-20-92 AUTHORIZED OPERATOR/AGENT: Beverly J. Williams  
(signature)

Beverly J. Williams, Engineering Technician

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

January 20, 1993

Anadarko Petroleum Corp  
Box 351  
Liberal KS 67905-0351

Humble A 5  
2130' FSL-1980' FEL  
Sec. 17-34-43W  
Morton County

Dear Ms. Beverly Williams,


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760