

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-129-10485-0000

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 3/25/58 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM) *Interstate Unit WELL NO. 16 WELL LOCATION C NW SE COUNTY Morton

SEC. 17 TWP. 34S RGE. 43 ~~(E)~~ or (W) TOTAL DEPTH 4341 PLUG BACK TD 4298

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. 75-605-C

SURFACE CASING SIZE 7" SET AT .1264 CEMENTED WITH 450 SACKS

CASING SIZE 4-1/2" SET AT 4340 CEMENTED WITH 100 SACKS

PERFORATED AT 4236-4266

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ ± 4200'. Using tubing, top plug with 20 sxs cement. Load hole with lease water. Spot 20 sxs cement from 2900-2520' (casing leak squeezed at 2600' with 375 sxs). Shoot off casing at freepoint. Spot 25 sxs cement at (If additional space is needed use back of form) (Over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? Drillers Log Filed
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sarcents Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)
M. L. Pease, Division Production Engineer

*Formerly Panhandle Eastern Pipe Line Company
HUMBLE 02

DATE: August 28, 1986

9-2-86
SEP 2 1986

freepoint, 25 sxs from 1300-1100', 25 sxs from 650-470', and 10 sxs from 70-0'. Spot 9 ppg mud between all cement plugs in the surface casing. Cut off casing below ground level. Weld on steel plate. Restore location. Cement type will be 60/40 Poz with 6% gel.



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE

DEC 2 '86

EXPIRES

September 2, 1986

WELL PLUGGING NOTICE

Interstate Unit #16 (SWD)
C NW SE
Sec. 17-34S-43W
Morton County

Anadarko Production Corporation
P. O. Box 351
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760
five days prior to plugging the well (KAR-82-3-113).