

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

RECEIVED FORM CP-1  
KANSAS CORPORATION COMMISSION  
REV. 03/92

JAN 18 1995

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

CONSERVATION DIVISION  
WICHITA, KS

API # 15-129-20,458 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE INTERSTATE "B" WELL# 6 SEC. 17 T. 34S R. 43 (XXXX West)

- - C - SW SPOT LOCATION/QQQQ COUNTY MORTON

1320 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL     GAS WELL X D&A     SWD/ENHR WELL     DOCKET#    

CONDUCTOR CASING SIZE     SET AT     CEMENTED WITH     SACKS

SURFACE CASING SIZE 8 5/8" SET AT 368' CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 1334' CEMENTED WITH 500 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 1242-1250', 1256-58', 1266-76'

ELEVATION 3548'/3553' T.D. 1335' PBSD 1300' ANHYDRITE DEPTH      
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR     CASING LEAK     JUNK IN HOLE    

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS. LOAD HOLE W/9 PPG MUD AND ESTABLISH CIRC DOWN 2-1/16" TBG. MIX AND SPOT 2 SXS HULLS AND 20 SXS CLASS H CMT (YLD 1.06cuft/sk) FROM 1300-1060'. DISPLACE CMT W/150 GAL WTR. TOH W/TBG TO 450'. SPOT 15 SXS CMT FROM 450-270'. DISPLACE CMT W/60 GAL WTR. TOH W/TBG. SPOT 5 SXS CMT 40-4'. CUT OFF 4-1/2" & 8-5/8" CSG 4' BELOW GL AND CAP. PERMANENTLY INSCRIBE THE DATE OF PLUGGING AND WELL NAME ON TOP OF CAP. RESTORE LOCATION AND SUBMIT FINAL RECLAMATION NOTICE TO BLM.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?     IS ACO-1 FILED? LOG FILED

If not explain why?    

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MARVIN JOHNSON PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-13-95 AUTHORIZED OPERATOR/AGENT: J.V. ASHTON (signature) DIV. PROD. MGR.

8/95

1/95

1)



## Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 19, 1995

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Interstate "B" #6  
API 15-129-20,458  
1320 FSL 1320 FWL  
Sec. 17-34S-43W  
Morton County

Dear Marvin Johnson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,  


David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760