

15-129-00152-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # Spud 10-19-64 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE INTERSTATE "I" WELL# 2 SEC. 10 T. 34 S. R. 43 (XXXX/West)

- C - NW - SE SPOT LOCATION/QQQQ COUNTY MORTON

1980 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

600 FEET (in exact footage) FROM (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  X D&A  SWD/ENHR WELL  DOCKET#                     

CONDUCTOR CASING SIZE                      SET AT                      CEMENTED WITH                      SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1265 CEMENTED WITH 600 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 1365 CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 1290'-1293'

ELEVATION 3535 / -- T.D. 5130 PBTD 1365 ANHYDRITE DEPTH --  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS, LOWER 2" TBG TO PBTD, LOAD HOLE W/9 PPG MUD AND EST CIRC DWN TBG, MIX AND SPOT 2 SXS HULLS AND 20 SX CLASS H CMT FROM 1365'-1265', PULL FREE POINT ON 4.5" CSG AND CUT OFF, SPOT 20 SX CMT FROM CUT OFF POINT TO 50' ABOVE CUT OFF, TOH WITH TBG, TO 40' SPOT 20 SXS CMT 40'-4', CUT OFF 8-5/8" CSG 4' BELOW GL AND CAP, PERMANENTLY INSCRIBE THE DATE OF PLUGGING AND WELL NAME ON TOP OF CAP, RESTORE LOCATION, NOTIFY BLM FOR LOCATION INSPECTION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

12-20-96

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. TERRY LEWIS PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67950

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-17-96 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (Signature) DIV. PROD. ENGR.



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

December 20, 1996

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Interstate "I" #2  
API 15-N/A  
1980 FSL 600 FWL  
Sec. 10-34S-43W  
Morton County

Dear Mr. Terry Lewis,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760